

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Menominee COUNTY


T 35 N R 25 W

DESCRIPTION OF CORNER Section corner for sections ^{30/29} 31/32

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6/10/70, F. J. Bray with B. McDonald

WITNESSES TO CORNER..... 7" W. Birch (S. 30) (NET) N 43° W, 11.3'



6" W. Birch (S. 29) (NET) N 89° E, 14.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners one mile to north, south, and east and 1/4 corner 1/2 mile to west. Notes of original survey do not check for swamp edges.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE

6/29/70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68