

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>35</u> N. S., R. <u>25</u> E. W.	<u>I-10, I-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 8 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- I-10 East 1/4 corner, Section 27; Wood Post, Cedar 14 - N8°W - 21 lks.; Fir 10 - S39°W - 18 lks.
- I-11 S.E. section corner - Section 27; M.D.S.H. plans for State Highway M-35; 1" iron pipe, 5" Cedar - N17°E - 30.06'; 5" Cedar - S36°W - 17.75'; T. Pole - S13°E - 9.05'. Old Wells State Park map (1935) R.R. spike in centerline of road replaced by standard monument; 6" Cedar - North - 33.4'; 6" Spruce - S20°W - 44.8'; Double Cedar - N45°W - 38.0'.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- I-10 Set M.P.O.L. between the N.E. and S.E. section corners of Sec. 27. No sign of O.B.T.'s Old park boundary posts are in an old telephone line about 45 ft. west but no record of them having been set by survey and no other support for other than a straight line.
- I-11 Found 1" pipe beside broken concrete monument buried in the centerline of an old E-W road grade. Blased 6" Cedar with a nail and roofing cap is S36°W - 17.75' and a down cedar blased and with a nail and roofing cap - N17°E - 30.06' for two M.D.S.H. witnesses. Also found remains of the double cedar Wells Park witness - N45°W - 38'. Set a new DNR monument in a concrete cylinder 3" in diameter and buried the old monument & pipe beside it

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- I-10 1" pipe, 4" aluminum cap; 5" Cedar - N38°W - 16.9'; 10" Cedar - S87°E - 10.9'; 9" Cedar - S11°W - 7.8'; 18" Y. Birch - S53°W - 5.9'.
- I-11 1" pipe, 4" aluminum cap in concrete 3" diameter; 13" W. Pine - S67°E - 75.5'; 6" Cedar - S35°W - 17.5'; 9" Bl. Ash - N12°E - 32.2'; 8" Cedar - N23°E - 30.2'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558