

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>35</u> N. S., R. <u>25</u> E. W.	<u>H-11</u>
2. PROPERTY CONTROLLING IN SECTION <u>27</u>	T. <u>35</u> N. S., R. <u>25</u> E. W.	<u>14, 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 21 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-11 South $\frac{1}{4}$ corner - Section 27; Wood Post, Fir 8 - S63°W - 4 lks., Cedar 8 - N56°E - 12 lks., searched but found nothing.
- 14 South 1/16 corner on the east boundary of Section 27; not previously established.
- 16 East 1/16 corner on the south section line - Section 27; DNR Map 1935, set standard monument in line with new fence south.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-11 Set on line with and double the distance between the S.E. section corner and the E. 1/16 corner on the south section line of Sec. 27. This position falls in the centerline of an abandoned road grade east and is very near mid point between the S.E. and S.W. section corners of Sec. 27 but it is not on a straight line for the mile.
- 14 Set M.P.O.L. between the E. $\frac{1}{4}$ corner and the S.E. section corner of Section 27.
- 16 Found 4" diameter concrete monument (broken) in centerline of road - old fence south - replaced with DNR monument - buried old concrete monument beside it.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-11 1" pipe, 4" aluminum cap; 8" Balm of Gilead - S76°W - 8.3'; 4" Balm of Gilead - S77°E - 4.2'; 9" Cedar - N33°W - 26.3'; 9" Balsam - N21°W - 37.3'.
- 14 1" pipe, 4" aluminum cap; 7" Cedar - N64°E - 13.0'; 6" Cedar - S83°E - 34.3'; 9" Cedar - S61°E - 27.2'; 7" Cedar - S5°E - 16.0'; Centerline M-35 - West - 52.0'.
- 16 1" pipe, 4" aluminum cap buried in road; 15" Cedar - N20°E - 13.0'; 4" W. Birch - N45°W - 21.2'; 5" Cedar - S72°E - 67.8'; 5" W. Spruce - S54°E - 73.0'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558