

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*MENOMINEE*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	T. <u>35</u> N. <u>25</u> E. _____ S., R. _____ W. _____	<u>8, 10, 14, 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 27, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 8 - W 1/16 corner on the E-W 1/4 line of Section 10; not previously established.
- 10 - S 1/16 corner on the West Section line of Section 10; not previously established.
- 14 - S 1/6 corner on the East Section line of Section 10; not previously established.
- 15 - W 1/16 corner on the South boundry of Section 10; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8- Set M.P.O.L. between the West 1/4 corner and the center of Sec. - Section 10.
- 10- Set M.P.O.L. between the West 1/4 corner and the S.W. Sec. corner of Section 10.
- 14- Set M.P.O.L. between the S.E. Sec. Corner and the E 1/4 corner of Section 10.
- 15- Set M.P.O.L. between the S 1/4 corner and the S.W. Section corner of Section 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 8 - 1" pipe, 4" aluminum cap; 12" cedar - S9°E - 63.2'; 5" w. birch - N83°E - 27.5'; 4" w. birch - N39°E - 33.4'; 4" balsam - N61°W - 11.8'.
- 10 - 1" pipe, 4" aluminum cap; 8" r. maple - S78°W - 26.5'; 9" w. birch - N6°W - 23.6'; 12" ash - N32°E - 27.1'; 8" w. birch - S68°E - 10.7'.
- 14 - 1" pipe, 4" aluminum cap; 9" w. spruce - S22°W - 49.0'; 6" balsam - S39°E - 44.9'; 8" ash - N82°E - 36.6'; 12" ash - N11°E - 52.6'.
- 15 - 1" pipe, 4" aluminum cap; 5" twin red maple - N70°E - 18.3'; 6" r. maple - S9°W - 13.0'; 5" r. maple - S82°W - 12.7'; 6" balsam - N6°W - 31.8'.

SIGNED BY \_\_\_\_\_

David B. Babbitt

DATE \_\_\_\_\_

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: