

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MEMORINEE

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. _____ E. _____ S., R. _____ W. _____		
2. PROPERTY CONTROLL- 10 _____ T. 35 _____ N. 25 _____ E. _____ ING IN SECTION _____ , T. _____ S., R. _____ W. _____		5, 9, 11, 12
3. MISCELLANEOUS _____ T. _____ N. _____ E. _____ PROPERTY IN SECTION _____ , T. _____ S., R. _____ W. _____		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 27, \_\_\_\_\_, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 5 - N 1/6 corner on the N-W 1/4 line of Section 10; not previously established.
- 9 - E 1/6 corner on the E-W 1/4 line of Section 10; not previously established.
- 11 - SW 1/6 corner of Section 10 (center of the S.W. 1/4); not previously established.
- 12 - S 1/6 corner on the N-S 1/4 line of Section 10; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 - Set M.P.O.L. between the center of Section and the N 1/4 corner of Section 10.
- 9 - Set M.P.O.L. between the center of Section and the E 1/4 corner of Section 10.
- 11 - Set at the computed center of the S.W. 1/4 of Section 10 by closed traverse.
- 12 - Set M.P.O.L. between the center of Section and the S 1/4 corner of Section 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 5 - 1" pipe, 4" aluminum cap; 9" cedar - S40°E - 11.5'; 5" cedar S10°W - 17.3'; 6" cedar - N68°W - 13.1'; 5" cedar S72°W - 2.9'.
- 9 - 1" pipe, 4" aluminum cap; 8" w. birch - N27°W - 46.5'; 30" h. maple - N78°E - 90.5'; 3" scotch pine - S58°E - 55.9'; 8" aspen - S32°W - 52.7'.
- 11 - 1" pipe, 4" aluminum cap; 8" w. birch - S15°W - 2.4'; 9" r. maple - S72°W - 9.5'; 8" w. birch - N35°W - 10.8'; 8" r. maple - S67°E - 12.6'.
- 12 - 1" pipe, 4" aluminum cap; 4" balsam - S45°E - 7.8'; 9" balsam - S26°W - 17.4'; 9" h. maple - N67°W - 28.4'; 4" h. maple - N49°E - 12.2'.

SIGNED BY

*David B. Babbitt*

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)