

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MENOMINEE

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>35</u> N. S., R. <u>25</u> E. W.	H-4 & H-5
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 27, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-4 - Center 1/4 corner of Section 10; not previously established.
- H-5 - S 1/4 corner of Section 10; iron pipe. Found in a 1956 survey by Billy D. Buckler, R.L.S. but not recorded at that time.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-4 - Set at the intersection of the N - S and E - W 1/4 lines of Section 10.
- H-5 - Set at the position of a pipe found in a survey by Billy D. Buckler R.L.S. in 1956. This pipe has since been removed but we placed a mon. at the same position by retracing his 1956 survey. Measurements East & West are reasonable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-4 - 1" pipe, 4" aluminum cap; 6" ash - N8⁰W - 35.3'; 9" ash - N29⁰E - 5.0'; 4" ash - S85⁰E - 22.6'; 3" ash - S11⁰W - 15.2'.
- H-5 - 1" pipe, 4" aluminum cap; 4" h. maple - N27⁰W - 36.6'; 5" h. maple - N49⁰E - 35.5'; 9" w. birch - N89⁰E - 8.3'; 19" w. spruce S15⁰W - 53.1'.

SIGNED BY

David B. Babbitt

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: