

Menominee County

05-16-83
10-24-83

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>14</u> T. <u>35N</u> N. S., R. <u>25W</u> E. W.		<u>I-6</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 29, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-6 - West 1/4 Cor. of Sec. 14; Conservation Dept. Mon. (1" pipe with 4" brass cap) set by Billy D. Buckler 7-17-56; 7" Cedar - N13°W - 72½ Lks.; 6" Cedar - N86°E - 62 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-6 - Billy Buckler set a D.N.R. Mon. for this 1/4 Cor. in 1956. His notes indicate that it was his intent to set said Mon. mid point on line between the Sec. Cors. Area Forester Wallace Gunderson, of Stephenson, in attempting to use this Mon. at a later date notified me that, according to his measurement, it was not in fact at mid point. I had my survey crew check the position of this Mon. and we found it to be 54 Ft. North of mid point between the two Sec. Cors. From this it is obvious that some sort of error was made in setting said 1/4 Cor. Mon.

It was, therefore, determined that this 1/4 Cor. Mon. should be moved (Continued on back)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 - D.N.R. Mon. w/Brass Cap; 8" Cedar - N30E-29.4'; 11" Cedar - N68W - 24.0'; 9" Cedar - S34W - 24.1'; 4" Bl. Ash - S62E - 26.55'.

SIGNED BY David B. Babbitt DATE 10-24-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____