

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 35N N. S., R. 25W E. W.	J-6
2. PROPERTY CONTROL- 14 ING IN SECTION _____	T. 35N N. S., R. 25W E. W.	3
3. MISCELLANEOUS 14 PROPERTY IN SECTION _____	T. 35N N. S., R. 25W E. W.	9-A
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**MENOMINEE
CO.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 6, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

J-6 - Center 1/4 of Section 14; not previously established.

3 - North 1/16 cor. on the West Sec. line of Sec. 14; nothing of record.

9-A - Point on E-W 1/4 line of Sec. 14 on the East bank of the Cedar River; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-6 - Set at the intersection of the N-S and E-W 1/4 lines of Section 14 by closed traverse.

3 - Found small Sq. Cedar stake and occupied line to the West. Replaced stake with D.N.R. Mon.

9-A - Set Monument on line between the East and West 1/4 Cors. of Sec. 14 1021.8' West of the East 1/4 Cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-6 - 1" pipe 4" aluminum cap; 10" Cedar - S45°W - 26.9'; 10" Cedar - N65°W - 24.1'; 3" W. Spruce - N50°E - 23.1'; 4" W. Ash - S29°E - 9.4'.

3 - D.N.R. Mon., 9" Cedar - N21°E - 29.0'; 9" Cedar - N18°W - 21.25'; 8" Cedar - S03°E - 21.6'; 14" Cedar - S52°W - 33.45'.

9-A - D.N.R. Mon.; 6" Cedar - S57°W - 17.4'; 9" Cedar - S10°W - 16.5'; 13" Cedar - S01°E - 28.9'; East bank of Cedar River - West - 30' center line old M-35 - East - 26'.

SIGNED BY _____

David B. Babbitt

DATE _____

3-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: