

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code \neq
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>23</u> T <u>35N</u> R <u>25W</u>	<u>12, 8, 11.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, David B. Babbitt in a field survey on 12/19, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 12. South 1/16 corner on the N-S 1/4 line of Section 23. No previous record.
- 8. West 1/16 corner on the E-W 1/4 line of Section 23. No previous record.
- 11. SW 1/16 corner (center of the SW 1/4) of Section 23. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 12. Set 44.98' west of park monument as shown on a drawing of survey by Dean C. Dela Mater, RLS, showing the park boundary in this area. The drawing is not dated but from other correspondence on file, it must have been drawn in 1951. This monument is as near the position, by correct procedures for a fractional section subdivision, as could be expected with the equipment and procedures used in 1951. A bolt of unknown origin is 20.65' west of this point.
- 8. Set MPOL between the W1/4 corner and the center post monument of Section 23.
- 11. Set at the computed center of the SW 1/4 of 23 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-------------------------|-------------------------|--------------------------|
| 12. 6" cedar S1E, 20.0' | 8. 6" cedar S81W, 46.1' | 11. 4" cedar N36E, 18.5' |
| 11" cedar S30W, 16.0' | 5" cedar N73W, 38.55' | 6" cedar S67E, 30.6' |
| 8" cedar S85W, 27.5' | 14" cedar N20E, 52.2' | 8" cedar S71W, 35.9' |
| 7" cedar N10W, 12.5' | 4" balsam S3E, 42.4' | 8" cedar N63W, 35.3' |
| DNR Monument. | DNR Monument. | DNR Monument. |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by David B. Babbitt Date 1-27-87
 Surveyor's Michigan License No. 21558