

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T <u>35N</u> R <u>25W</u>	<u>8, 4, 6.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on 2/26, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 8. West 1/16 corner on the E-W $\frac{1}{2}$ line. No previous record.
- 4. NW 1/16 corner of Section 34 (center of the NW $\frac{1}{4}$). No previous record.
- 6. NE 1/16 corner of Section 34 (center of the NE $\frac{1}{4}$). No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 8. Set MPOL between the West $\frac{1}{4}$ corner and the center of Section 34 by closed traverse.
- 4. Set at the center of the NW $\frac{1}{4}$ of Section 34 by closed traverse.
- 6. Set at the computed center of the NE $\frac{1}{4}$ of Section 34 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------|------------------------|--|
| 8. DNR Monument. | 4. DNR Monument | 6. DNR Monument |
| 5" cedar, N78E, 19.5' | 5" cedar, S67E, 29.0' | 4" cedar, N4E, 98.3' |
| 9" cedar, S55E, 7.7' | 7" cedar, S9W, 26.8' | 10" tw. cedar, N45E, 66.8' |
| 8" cedar, S6W, 33.7' | 6" cedar, S52W, 46.95' | 8" cedar, S29E, 38.2' |
| 8" cedar, N45W, 18.3' | 4" cedar, N69W, 37.8' | 7" cedar, West, 34.3' |
| | | Conc. mon. marked "State of Michigan", N34E, 72.95'. |

Signed by David B. Babbitt
Surveyor's Michigan License No. 21558

Date 3-25-87