

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located In:

Corner Code I-5

- | | | | | | |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey | T | 35N | R | 25W | I-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 10/19/87, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-5. NE section corner of Section 15. Mich. Dept. of Conservation. 7/17/56.
 Set 1" pipe w/4" brass cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5. Found 1" pipe with 4" brass cap marked Mich. Dept. of Conservation, Forestry Division. Both 1956 NBT's present but the balsam is dead and down and the cedar has been cut leaving a 3½' high stub in place. Re-witnessed monument as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5. 1" pipe w/4" brass cap.
 12" cedar, S76E, 76.9'
 10" cedar, S35E, 54.7'
 10" cedar, N22E, 19.8'
 6" balsam, S31W, 11.6'

Signed by David B. Babbitt Date 12-3-87
 Surveyor's Michigan License No. 21558