

OK. Babbitt

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee (County) Located In: Corner Code #/
1. Public Land Survey T R
2. Property Controlling in Section S 27 T 35N R 25W 6, 9, 13, 2.
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, David Babbitt, in a field survey on 11/10/87, 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a 6x6 grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

- 6. NE 1/16 corner of Section 27. No previous record.
9. E 1/16 corner of Section 27. No previous record.
13. SE 1/16 corner of Section 27. No previous record.
2. E 1/16 corner on the North section line of Section 27. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 6. Set at the computed center of the NE 1/4 of Section 27 by closed traverse.
9. Set MPOL between the east 1/4 corner and the center of Section 27.
13. Set at the computed center of the SE 1/4 of Section 27 by closed traverse.
2. Set MPOL between the north 1/4 corner and the NE section corner of Section 27.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 6. DNR Monument 13" spruce N17W 18.8'
9. DNR Monument 4" cedar S45W 20.8'
13. DNR Monument 5" cedar S73E 1.1'
2. DNR Monument 3" cedar S52W 2.3'
12" cedar S86E 25.9'
5" cedar N66W 20.2'
4" balsam N45E 21.1'
4" cedar N30W 9.3'
3" y.birch S26W 8.3'
4" cedar N32E 18.7'
8" cedar N30W 21.9'
6" maple S69E 21.6'
8" w.ash S77W 22.2'
6" cedar S61E 20.7'
5" cedar N58W 30.8'
4" balsam N82E 44.3'

Signed by David B. Babbitt

Date 12-3-87

Surveyor's Michigan License No. 21558