

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <i>##</i>
1. Public Land Survey	T <u>35N</u> R <u>25W</u>	<u>K-3, L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>12</u> T <u>35N</u> R <u>25W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3											3	3	3
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Paul R. Bressette, in a field survey on January 23, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-3. Section Corner common to Sections 1, 2, 11, and 12. Restored in 1956 by Billy Buckler, RLS. Set 1" iron pipe w/ 4" brass cap. 9" Cedar N 73° W 32 lks. 9" Cedar S 16° E 36 lks.

L-3. Quarter Corner common to Sections 1 and 2. 1959, origin unknown. Square 4" cedar post 3" Cedar N 15° E 6.25'; 4" Spruce S 62° E 12.48'; 4" Cedar S 10° E 14.60'. Found in DNR District 3 files of corners set by others.

1. West one sixteenth Corner common to Sections 1 and 12. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3. Found monument and witnesses as described. Both BT's alive and standing with blazes overgrown but visible. Rewitnessed monument as found.

L-3. Found 1/2" iron pin in concrete. Bearing and distance to above NBT's checks well. Corner also shown on plat of Tracy's Indian Bay Subdivision recorded in Liber C, p. 42 and 43. Distance to found plat monument checks closely.

1. Corner set midpoint and on-line between the Northwest and North Quarter corners of Section 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3. 1" iron pipe w/ 4" brass cap. 14" Cedar S 16° E 24.15' (old NBT); 14" Cedar N 77° W 20.9' (old NBT); 8" Cedar (S 1, NBT) N 53° E 7.4'; 4" Spruce (S 11, NBT) S 31° W 15.55'.

L-3. 1/2" iron pin in concrete. 7" Cedar (1/4 S, NBT) N 10° E 9.8'; 8" Cedar (1/4 S, NBT) S 40° E 17.95'; 5" Balsam (1/4 S, NBT) S 11° W 35.55'; 8" Cedar (1/4 S, NBT) N 62° W 23.9'.

1. DNR monument. 5" W. Birch (1/16, BT) N 87° E 7.8'; 8" Cedar (1/16, BT) S 43° W 17.5'; 10" cedar (1/16, BT) N 64° W 48.7'; 9" Ash (1/16, BT) N 03° W 45.9'.

Signed by Paul R. Bressette Date January 28, 1992
 Surveyor's Michigan License No. 37270

