

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee (County) Located In: Corner Code --//
1. Public Land Survey T ___ R ___
2. Property Controlling in Section S 12 T 35N R 25W 8, 10, 11
3. Miscellaneous Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Paul R. Bressette, in a field survey on January 21, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and symbols like 'O' and 'X'.

A. Description of original monument and accessories and/or subsequent restoration:

- 8. West One sixteenth Corner of Section 12. Not set in original survey, no evidence of subsequent establishment.
10. South One sixteenth Corner common to Sections 11 and 12. Not set in original survey, no evidence of subsequent establishment.
11. Southwest One sixteenth Corner of Section 12. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 8. Set midpoint and on line between the East Quarter Corner and the Center Quarter Corner of Section 12. Plat monument shown as Southwest Corner of Gov't Lot 2 on Tracy's Indian Bay Subdivision was rejected as Center Quarter Corner. Monument is 64.42 feet east of North-South quarter line and 50.84 feet south of calculated position.
10. Set mid-point and on line between the Southwest and West Quarter Corners of Section 12.
11. Set at the intersection of the South and West One-sixteenth lines.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 8. DNR monument. 10" Cedar (1/16,BT) N 83° E 52.0'; 6" Balsam (1/16,BT) S 76° E 37.05'; 6" Cedar (1/16,BT) S 09° E 44.2'; 12" W. Ash (1/16,BT) S 04° W 53.25'. Monument falls ±30' southeast of the centerline of M-35.
10. DNR monument. 6" Ash (1/16,BT) N 65° E 25.1'; 6" Ash (1/16,BT) S 32° E 32.25'; 6" Cedar (1/16,BT) S 43° W 43.3'; 7" Ash (1/16,BT) N 26° W 2.9'.
11. DNR monument. 5" Cedar (1/16,BT) N 16° E 14.05'; 8" Cedar (1/16,BT) S 61° E 18.95'; 9" Cedar (1/16,BT) S 21° W 7.85'; 5" W. Ash (1/16,BT) N 20° W 23.3'.

Signed by Paul R. Bressette Surveyor's Michigan License No. 37270

Date January 28, 1992

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1976

