

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee (County) Located In: Corner Code //
1. Public Land Survey T 35N R 25W K-5, L-5
2. Property Controlling in Section S 12 T 35N R 25W 15
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Paul R. Bressette, in a field survey on January 21, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and three circles in row 6, column J.

A. Description of original monument and accessories and/or subsequent restoration:

- K-5. Section Corner common to Sections 11, 12, 13, and 14. Restored in 1956 by Billy Buckler, RLS. Set 1" iron pipe with 4" brass cap. 9" Cedar N 01° W 50 lks. 8" Cedar S 19° E 32 lks.
L-5. Quarter Corner common to Sections 12 and 13. Restored in 1970 by George Wilson, RLS. Set 4" round concrete monument, no witnesses.
15. West One sixteenth Corner common to Sections 12 and 13. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-5. Found monument and witnesses as described. NW BT is blown down. Rewitnessed monument as found.
L-5. Found monument as described. Corner is shown on Certified Survey #146, and subsequently on Certified Surveys 154, 155, 174, 175, and 196. Rewitnessed monument as found.
15. Corner set midpoint and on-line between the Southwest and South Quarter Corners of Section 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5. 1" iron pipe w/ 4" brass cap. 6" Black ash (S 12,NBT) N 18° E 33.9'; 9" Cedar (S 13,NBT) S 17° E 29.7'; 9" Yellow birch (S 14,NBT) S 41° W 30.35'; 5" Black ash (S 11,NBT) N 29° W 9.3'.
L-5. 4" Round concrete monument. 9" Hemlock (1/4S,NBT) N 67° E 10.6'; 12" W. Pine (1/4S,NBT) S 19° E 18.35'; 13" W. Pine (1/4S,NBT) S 13° W 16.5'; 6" Cedar (1/4S,NBT) N 79° W 11.9'.
15. DNR monument. 6" Cedar (1/16,BT) N 45° E 5.7'; 6" Cedar (1/16,BT) S 41° E 16.0'; 4" Cedar (1/16,BT) S 04° E 18.8'; 12" Cedar (1/16,BT) N 73° W 13.15'.

Signed by Paul R. Bressette Date January 28, 1992

Surveyor's Michigan License No. 37270

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

