

SURVEY & REMONUMENTATION

JAN 09 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 7/13, 2000
MEL DAVIS RLS
Chairman

For corners in
MENOMINEE

(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>35</u> N R <u>25</u> W	E-09
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Book 6 Page 187

RECEIVED FOR RECORD
13 DEC 2000 10:16:09 A
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on June 26, 1900 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Birch, 8" - N20°E - 05 lks.; Birch, 8" - N71°W - 06 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1970: L.C.R.C. No. 764, Volume 3, by Frank J. Bray, RLS, states that a 1/2" x 12" re-rod was driven in blacktop road, replaced from measurements to fence corners as recorded by the Menominee County Road Commission in 1949.
- 1993: Private records of William Lenca, RLS No. 26461, indicate that the corner described in LCRC No. 764, Vol. 3 was recovered and replaced with a 5/8" x 24" Iron Rod & B.T.'s: W. Birch, 6" - N33°E - 79.12'; Maple, 6" - S27°E - 43.70'; W. Pine, 12" - S53°W - 70.35'; Tamarack, 9" - N27°W - 61.07'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch x 24 inch iron rod and 4 B.T.'s as described in my notes from a 1993 field survey. The corner falls in the centerline of an East - West County Road and in line with an old fence line North and the centerline of a lane running South. This corner position fits well with measurements to other corners in the area, and with existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N57°E	51.29 feet	1' W. of PP
7" dia. Maple (Ex. B.T.)	S27°E	43.70 feet	Scr. NBT
14" dia. White Pine (Ex. B.T.)	S53°W	70.35 feet	Scr. NBT
10" dia. Tamarack (Ex. B.T.)	N27°W	61.07 feet	Scr. NBT
Metal Survey Sign Post	North	38.8 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date June 30, 2000