

# SURVEY & REMONUMENTATION

JAN 09 2001


## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 7/13, 2000  
Mr. Davis RLS  
Chairman

Book 6 Page 193

For corners in <u>MENOMINEE</u> <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T <u>35N</u> R <u>25W</u>	G-10	
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____



Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on June 27, 1900 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1848: Original Survey by James H. Mullett - B.T.'s - Beech, 18" - S10°W - 18 lks.; Beech, 12" - N37°E - 20 lks. All original evidence for this corner has been destroyed by logging activities.
- 1970: L.C.R.C. No. 741, Volume 3, by Frank Bray, RLS, states that a 1" pipe with 4" brass cap was placed at fence corner. George Foley, landowner, claims an original B.T. to have been present years ago. Squared wood post at fence corner. B.T.'s: 12" H. Maple - N37°W - 16.1 feet; 4" Ironwood - S34°W - 23.0 feet.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

We found a 1 inch diameter iron pipe with a 4 inch diameter aluminum cap at an ancient fence corner, along with the 2 B.T.'s as described in LCRC No. 741, Vol. 3 (see part A). This corner has been accepted and used for many years, and is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Accepted Existing 1" dia. Iron Pipe/4" Aluminum Cap stamped for corner location.

10" dia Maple	N10°E	23.04 feet	Scr. NBT
9" dia. Hard Maple	N76°E	51.30 feet	Scr. NBT
12" dia. Hard Maple	S13°E	32.43 feet	Scr. NBT
6" dia. Bluebeech	N83°W	12.24 feet	Scr. NBT
Metal Survey Sign Post	West	0.8 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date June 30, 2000