

FEB 11 1998

Approved by Menominee County
Land Survey Renomination
Four Group Under Act 345 Of
P.A. of 1998 On 12/30 1997
Mr. David RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>25W</u>	<u>L-07</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED FOR RECORD
97 DEC 30 PM 4:06
PAGE # 628, BKS
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on July 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Birch, 6" - N63°W - 29 lks; Cedar, 10" - S22°E - 36 lks. All original evidence for this corner has been destroyed by logging activities and county road improvements.
- 1958: Plat of Survey by Robert Olsen shows this corner as it relates to other corners in Gov. Lot 4, Sec. 13, T35N-R25W. The corner monument is described as "Steel Rod". No witnesses are given.
- 1970: Plat of Survey by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 13, T35N-R25W, and describes it as "found pin". No B.T.'s are given.
- 1991: L.C.R.C. No. 928 recorded by William Lenca, RLS No. 26461, states "Found 5/8" dia. Iron Rod in location indicated on several old survey maps. B.T.'s: 16" Cedar - N66°E - 10.17'; 5" Cedar - S14°W - 7.44'; 10" Cedar - N76°W - 7.57'; 20" Cedar - N16°E - 11.80'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch diameter iron rod as described in L.C.R.C. No. 928 (see part A) at an ancient fence corner and in line with county road centerlines East and South. This position fits with measurements to corners shown in Robert Olsen's 1958 survey and with those shown in George Wilson's 1970 survey. This corner position has been used by local surveyors for at least 39 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

16" dia. Cedar	N66°E	10.17 feet	Scr. NBT
5" dia. Cedar	S14°W	7.44 feet	Scr. NBT
10" dia. Cedar	N76°W	7.57 feet	Scr. NBT
20" dia. Cedar	N16°E	11.80 feet	Scr. NBT
Metal Survey Sign Post	West	1.15 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date July 18, 1997

628