

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/13 199 ?

Mr. David RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

<u>MENOMINEE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T35N R 25W	<u>M-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

97 DEC 22 AM 11:25
BOOK 569 BK 5
REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

GLO NOTES STATE THAT THIS IS NOT THE SAME AS COR. A-2 T35N-R24W

I, William Lenca, in a field survey on June 24, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by James H. Mullett - B.T.'s - Cedar, 8" - N61°W - 21 lks.; Cedar, 10" - S67°W - 31 lks. All original evidence for this corner has been destroyed by logging activities.
- 1970: Plat of Survey by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 1, T35N-R25W, and describes it as a concrete monument. The survey also shows that Wilson re-established the original Government Meanders in order to establish the Meander Corner on the East Line of Section 1. B.T.'s: 4" Cedar - North - 2.2'; 4" Cedar - West - 6.2'; 4" Cedar - South - 14.6'.
- 1992: CERTIFIED SURVEY No. 775 by William Lenca, RLS NO. 26461, shows this corner as it relates to other corners in Section 1, T35N-R25W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a concrete monument matching the position as shown in George B. Wilson's 1970 Plat of Survey. His witnesses had been destroyed by logging activities. The corner monument is 3429.26 feet South of the Northeast Corner of Section 1, T35N-R25W, which matches closely with the GLO distance of 3432 feet. The total distance from the NE Corner of Section 1 to the Meander Corner on the East Line of Section 1 measures 4287.34 feet, compared to the GLO distance of 4290 feet. Since it appears that this corner was established proportionately between the NE Corner and the Meander Corner, we accepted the position of the concrete monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 4 inch diameter concrete monument with 5/8" dia. rod in center:			
10" dia. Cedar	N29°E	32.61 feet	Scr. NBT
9" dia. Cedar	S71°E	39.95 feet	Scr. NBT
8" dia. Cedar	N85°W	60.84 feet	Scr. NBT
5" dia. Cedar	N37°W	20.77 feet	Scr. NBT
Metal Survey Sign Post	North	1.1 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date July 18, 1997

569