

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>35N</u> R <u>25W</u>	<u>08</u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
2. Property Controlling in Section	S <u>20</u> T <u>35N</u> R <u>25W</u>	<u>11</u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

11 Feb 17 1999
 08 Feb 10 1999

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		●		21		22		23		24	
9				●									
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (08) Center quarter corner of Section 20. Not set in original survey, no evidence of subsequent establishment.
- (11) Southwest One-sixteenth corner of Section 20. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (08) Corner position established at the intersection of the north-south and east-west quarter lines of Section 20.
- (11) Corner position established at the intersection of the south and west one-sixteenth lines of Section 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------------|-------------------------------|
| (08) DNR monument | (11) DNR monument |
| 7" Ash S80E 25.3' (1/4S,BT) | 5" Ash N06E 15.5' (1/16S,BT) |
| 6" Elm S31E 27.85' (1/4S,BT) | 6" Ash S62E 13.4' (1/16S,BT) |
| 5" Ash S56W 7.15' (1/4S,BT) | 4" Ash S23W 18.15' (1/16S,BT) |
| 5" Ash N09W 15.25' (1/4S,BT) | 6" Elm N18W 23.0' (1/16S,BT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette Date _____
 Surveyor's Michigan License No. _____

For the Michigan Department of Natural Resources - Forest Management Division