

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>20</u> T <u>35N</u> R <u>25W</u>	<u>6</u>
	S <u>20</u> T <u>35N</u> R <u>25W</u>	<u>8</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Feb 18 1999

I, Paul R. Bressette, in a field survey on _____, 19___ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- (6) Northeast One-sixteenth corner of Section 20. Not set in original survey, no evidence of subsequent establishment.
 - (8) West One-sixteenth corner of Section 20. Not set in original survey, no evidence of subsequent establishment.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (6) Corner position established at the intersection of the north and east one-sixteenth lines of Section 20.
 - (8) Corner position established mid-point and on-line between the west and center quarter corners of Section 20.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|-------------------------------------|-----------------------------------|
| (6) DNR monument | (8) DNR monument |
| 05" Spruce S77E 21.2' (1/16S, BT) | 12" Maple N14E 22.65' (1/16S, BT) |
| 05" Ash S21E 26.25' (1/16S, BT) | 06" Ash S53E 22.2' (1/16S, BT) |
| 11" W.Pine S58W 52.35' (1/16S, BT) | 07" Maple S49W 29.9' (1/16S, BT) |
| 10" W.Birch N25W 56.55' (1/16S, BT) | 09" Maple N89W 14.25' (1/16S, BT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division