

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-------------|---------------------------|----------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S <u>19</u> | T <u>35N</u> R <u>25W</u> | <u>4</u> |
| | S <u>19</u> | T <u>35N</u> R <u>25W</u> | <u>5</u> |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

5 Sep 08 1999
 4 Sep 09 1999

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (4) Northwest One-sixteenth corner of Section 19. Not set in original survey, no evidence of subsequent establishment.
 (5) North One-sixteenth corner of Section 19. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (4) Corner position established at the intersection of the north and west one-sixteenth lines of Section 19.
 (5) Corner position established mid-point and on-line between the north and center quarter corners of Section 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-------------------------------------|------------------------------------|
| (4) DNR monument | (5) DNR monument |
| 04" Ironwood N14E 21.55' (1/16S,BT) | 04" R.Maple N46E 51.6' (1/16S,BT) |
| 24" Sugar S35E 43.9' (1/16S,BT) | 10" R.Maple S06W 51.45' (1/16S,BT) |
| 07" Ironwood S07W 24.7' (1/16S,BT) | 08" R.Maple S46W 73.3' (1/16S,BT) |
| 11" Sugar S67W 24.4' (1/16S,BT) | 05" R.Maple N48W 46.3' (1/16S,BT) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division