

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>35</u> N R <u>25</u> W	<u>87</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>19</u> T <u>35</u> N R <u>25</u> W	<u>16</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

16 Sep 29 1999
 87 Feb 09 1999

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (B7) Quarter corner common to Sections 18 and 19. 1848: James H. Mullett, DS. Set wood post witnessed by: 8.Ash 8 S17W 5 lks.; 8.Ash 8 N42E 5 lks.
- (16) East One-sixteenth corner common to Sections 19 and 30. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (B7) No evidence of original survey or subsequent restoration found. Corner position reestablished mid-point and on-line between the northeast and northwest corners of Section 19, in accordance with the original survey, and is accepted as a careful and faithful REESTABLISHMENT of the position of the original corner.
- (16) Corner position established mid-point and on-line between the Southeast and South Quarter corners of Section 19.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------------------|------------------------------------|
| (B7) 1" iron pipe w/ plastic cap | (16) 5/8" rebar w/ plastic cap |
| 6" B.Ash N09E 56.25' (1/4S,NBT) | 14" Tamarack N25E 50.9' (1/16S,8T) |
| 5" B.Ash N66E 47.8' (1/4S,NBT) | 11" R.Maple S08E 37.0' (1/16S,8T) |
| 6" B.Ash S13E 57.5' (1/4S,NBT) | 08" Cedar S46W 50.8' (1/16S,8T) |
| 5" B.Ash S50W 30.1' (1/4S,NBT) | 10" W.Pine N31W 54.6' (1/16S,8T) |
- All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division