

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>35N</u> R <u>25W</u>	<u>C7</u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
	T <u> </u> R <u> </u>	<u> </u>	
2. Property Controlling in Section	S <u>19</u> T <u>35N</u> R <u>25W</u>	<u>7</u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jan 13 1998

I, Paul R. Bressette, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7			●										
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(E7) Section corner common to Sections 17,18,19 and 20. 1848: James H. Mullett, D.S. Set wood post witnessed by: Hemlock 6 S23E 7 lks.; Hemlock 6 N75W 13 lks. 1956: Billy D. Buckler, RLS. Set 1" iron pipe with brass cap witnessed by: 34" W.Pine stp. N72W 34 lks.; 24" W.Pine stp. N74E 52 1/2 lks. Two probable hemlock stump bottoms in place, traces of two stakes in soil. Distances to feature calls checked.

(7) North One-sixteenth corner common to Sections 19 and 20. 1970: Frank J. Bray, RLS. Set DNR monument mid-point and on-line between the Northeast and East Quarter corners of Section 19 witnessed by: 6" R.Maple N37E 22.5'; 6" R.Maple S06E 19.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E7) Found monument as described. Monument was rewitnessed as found, and is accepted as a faithful and careful PERPETUATION of the position of the original corner.

(7) Found monument and witnesses as described. Monument was rewitnessed as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E7) 1" iron pipe w/ brass cap
 6" W.Pine N56E 12.95' (S17,NBT)
 6" W.Pine S76E 13.2' (S20,NBT)
 5" W.Pine S23W 26.05' (S19,NBT)
 5" W.Pine N80W 10.6' (S18,NBT)
 All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.

(7) DNR monument
 11" R.Maple* N51E 22.6' (1/16S,BT)
 08" R.Maple* S06W 20.25' (1/16S,BT)
 07" R.Maple S74W 18.8' (1/16S,BT)
 09" R.Maple N70W 9.0' (1/16S,BT)
 * denotes Bray's BT's. All trees are blazed, scribed and painted. Measurements are to nail in side of tree, bearings are magnetic.



Signed by Paul R. Bressette
 Surveyor's Michigan License No. 37270

Date _____

For the Michigan Department of Natural Resources - Forest Management Division