

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>35</u>	T. <u>35</u> N. <u>X</u> , R. <u>26</u> <u>X</u> W.	K-11, K-12
2. PROPERTY CONTROLLING IN SECTION <u>35</u>	T. <u>35</u> N. <u>X</u> , R. <u>26</u> <u>X</u> W.	M.P.O.L. Betw. Codes 2 & K-11
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**MENOMINEE  
CO.**

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David E. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 23 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

K-11 N.E. Section corner; Wood post: Hem. 12 - S27°E - 26 lks; sugar 12 - N41°W - 09 lks.

K-12 East ¼ corner; Wood post; Aspen 10 - N20°E - 12 lks.; fir 8 - S12°W - 16 lks.

M.P.O.L. betw. codes 2 & K-11 - Point on north section line 669.9 feet west of N.E. Section corner.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

K-11 Set by double proportionate measurement using the ¼ corner ½ mile north and section corners 1 mile south - east and west.

K-12 Set M.P.O.L. between section corners ½ mile north and ½ mile south.

M.P.O.L. betw. codes 2 & K-11 - set by offset from random line.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-11 1" pipe with 4" aluminum cap; 11" beech - N71°W - 16.4'; 11" beech - N52°E - 19.3'  
9" cedar - N33°W - 66.6'

K-12 1" pipe with 4" brass cap; 6" cedar - S89°E - 16.75'; 5" cedar - N30°E - 10.35';  
squared and scribed 9" leaning cedar for post NW at mon. - 1.65'

M.P.O.L. betw. codes 2 & K-11 - 2' of 1½" pipe; 6" cedar - S79°E - 57.8'; 4" cedar - S2°E - 98.0'; both B.T.s on low-narrow ridge in cedar swamp.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David E. Babbitt  
CHIEF OF SURVEY PARTY  
MICHIGAN DEPARTMENT OF LAND SURVEYING

DATE 2-27-76