

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>36</u>	T. <u>35</u> N. S., R. <u>26</u> E. W.	<u>L-11</u>
2. PROPERTY CONTROLLING IN SECTION <u>36</u>	T. <u>35</u> N. S., R. <u>26</u> E. W.	<u>1, 3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MENOMINEE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on February 26 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

L-11 North  $\frac{1}{4}$  corner; Wood post - Tam. 6 - N14°E - 18 lks.; spruce 4 - S34°W - 17 lks.

- 1 W 1/16 cor. on north Section line.
- 3 N 1/16 cor. on west Section line.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L-11 Set M.P.O.L. between section corners  $\frac{1}{2}$  mile east and  $\frac{1}{2}$  mile west.

- 1 Set M.P.O.L. between the N $\frac{1}{4}$  corner and the N.W. section corner
- 3 Set M.P.O.L. between the west  $\frac{1}{4}$  corner and the N.W. section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 1" pipe with 4" aluminum cap; 7" spruce - N40°W - 15.3'; 6" spruce - S45°W - 12.6'; 5" spruce - N75°E - 9.0'.

- 1 1" pipe with 4" aluminum cap; 8" yellow birch - S26°E - 40.8 feet ; 10" white ash - S40°W - 25.1 feet
- 3 1" pipe with 4" aluminum cap; 4" cedar - N24°E - 12.9'; 6" cedar - S54°E - 20.65'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_