

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-- LOCATED IN-- CORNER CODE NUMBER
1. PUBLIC LAND SURVEY T. 35 N. 26 IX W. K-13, L-13
2. PROPERTY CONTROLLING IN SECTION 36 T. 35 N. 26 IX W. 15
3. MISCELLANEOUS PROPERTY IN SECTION T. N. S. R. E. W.
4. LOT NO. , RECORDED PLAT
5. PRIVATE CLAIMS

MENOMINEE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1974 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were in a field survey on July 31 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-13 Post Cedar 8 - N 68 E -27 Hem 16 - N 32 W - 10 Hem. 8 - S 49 E - 08 " 8 - S 30 W - 03
L-13 Post Sugar - N 54 E - 53 Beech - N 33 W - 46

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-13 Set in line with L-13 and 15 and an equal distance west. This location fits well for the calls for a narrow hem. ridge 2 chs. east and the swamp edge south as described in the original gov. notes. A large hem. stump is in position for the N.W. o.b.t.
L-13 Found 1/2" square iron rod reported to have been set from the original sugar B.T. by a surveyor named Jenkins in the early nineteen hundreds.
15 Found 1/2" Sq. rod and cedar stake not of record but presumed to have been set by surveyor Jenkins.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

ALL: 1" iron pipe with a 3 1/2" aluminum cap - all bearings magnetic

- K-13 7" cedar - S 63° W - 5.35' 6" " - N 13° W - 7.5' 4" " - S 73° E - 9.4'
L-13 4" H. Maple - N 30° W - 10.8' 6" H Maple W/crooked trunk - S 46° W - 21.2'
15 9" cedar - N10° - 3 12" cedar - S75°W- 13.8'

SIGNED BY DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE 7/13/75 (SEAL)