

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>34</u>	T. <u>35</u> N. S. R. <u>26</u> K. W.	<u>I-11, G-11, I-13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MENDHAM
GO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 24, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-11 N.E. Sec. Cor Wood Post Tam 6-S63°W - 14 lks. Tam 6-N63°E - 22 lks.	G-11 N.W. Sec. Cor. Wood Post Hem. 12 N42°E - 12 lks. Cedar 10 S13°E - 18 lks.	I-13 S.E. Cor. Wood Post Tam 5-N55°E 07 lks. Tam 7-N25°W 09 lks. Tam 8-S75°W 07 lks. Tam 8-S57°E 18 lks.
---	---	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-11 Set from 8" tam. stub with definite blaze (No scribe marks visible) for N.E. o.b.t. - stump remains in place for S.W. o.b.t. but almost completely rotted away	G-11 Set in line with fences south and east and in line with centerline roads north and west	I-13 Set from blazed tam stub for S.E. g.l.o. wit. line. Tree south at 11.77 chs. g.l.o notes say l.t. was at 13.90 but this has definite hack marks and is the right size etc.
---	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 1" pipe, 4" aluminum cap 3" cedar N80°W 20.1' 6" cedar N55°E 18.5' partly dead	G-11 1" pipe, 4" aluminum cap 10" cedar N45°W 41.0' 5" cedar N72°E 54.8' corner fence post south - 35.5'	I-13 1" pipe, 4" aluminum cap 6" cedar NW 18.0' 7" cedar West 25.4'
--	---	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE October 24, 1975