

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>27</u> T. <u>35</u> N. <u>26</u> E. R. <u>26</u> W.		<u>H-9, G-9, G-10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S. _____, R. _____, E. _____, W. _____		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S. _____, R. _____, E. _____, W. _____		_____
4. LOT NO. _____, RECORDED PLAT _____		_____
5. PRIVATE CLAIMS _____		_____

**MENOMINEE
CO**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 15 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

H-9 N $\frac{1}{4}$ cor.	G-9 N.W. Sec. Cor.	G-10 West $\frac{1}{4}$ cor.
Wood Post	Wood Post	Wood Post
Cedar 10 S56 $^{\circ}$ E - 11 lks.	Birch 12 - S70 $^{\circ}$ W - 24 lks.	Cedar 12 - N19 $^{\circ}$ E - 38 lks.
Birch 10 N65 $^{\circ}$ E - 13 lks.	Sugar 35 - N36 $^{\circ}$ E - 05 lks.	Birch 12 - N12 $^{\circ}$ W - 31 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-9 Set from Co. Road witnesses to road P.I. Falls in line with old fence line south.	G-9 Set in center of road intersection could find no other evidence of proper location	G-10 Set in line with E-W fence and in centerline N-S black top road. Old cedar stp. scribed "B.T." faces this point but not of record.
---	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 $\frac{1}{2}$ " pipe with plastic r.l.s. cap	G-9 $\frac{1}{2}$ " pipe with plastic r.l.s. cap	G-10 $\frac{1}{4}$ " re-rod in centerline black top road.
5" H. maple ($\frac{1}{4}$ s)(Nbt) N12 $^{\circ}$ E 48.0'	8" elm (S22)(NBT) N10 $^{\circ}$ E 151.3	8" cedar S61 $^{\circ}$ W 35.6'
10" Cedar ($\frac{1}{4}$ s)(NBT) N33 $^{\circ}$ W 50.6'	3" cedar (S28)(NBT) S42 $^{\circ}$ W 106.3	7" cedar N62 $^{\circ}$ W 50.7'
Cor. lies 1.0' north at highway centerline		5" stem of twin cedar S88 $^{\circ}$ E 44.75'
		24" cedar stp. scribed "B.T." S72 $^{\circ}$ W 22.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ DATE _____