

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>26</u> T. <u>35</u> N. <u>8</u> , R. <u>26</u> E. <u>W.</u>		I-9 J-9
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ S., R. _____ E. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**MENOMINEE
CO.**

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 9, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-9 N.W. Section Corner Wood Post Cedar 10 - N70°E - 30 lks. Hem. 10 - S35°W - 14 lks.	J-9 N¼ corner Wood Post Beech 12 - N62°E - 16 lks. Sugar 12 - S75°W - 29 lks.
--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-9 Set from Co. Road witness to road P.I. and centerline of road E-W-N could find no other evidence of the Sec. Corner location	J-9 Set from Co. Road witnesses to road P.I. - centerline of road E-W-N could find no other evidence of the ¼ corner location.
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 ½" pipe with plastic R.L.S. CAP west end of c.m.p. N23°W culvert 50.3 East end of c.m.p. N14°E - 47.8'	J-9 ½" pipe with plastic R.L.S. cap face of P.P. - N42°E - 47.9' T.P. & GWY pole S48°E - 46.2'
--	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE October 21, 1975
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)