

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---|--------------|--------------------|
| 1. PUBLIC LAND SURVEY <u>25</u> T. <u>35</u> N. S. R. <u>26</u> W. ^X | | K-9, K-10, L-9 |
| 2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S. R. _____ E. W. | | |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S. R. _____ E. W. | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

MENOMINEE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 9, 1975 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|--|---|--|
| K-9 N.W. Sec. Cor. Wood Post Cedar 10 -N58°W - 12 lks. Cedar 8 -S32°E - 44 lks. | K-10 W¼ cor. Wood Post Tam 6 - S65°W - 24 lks. Tam 4 - S25°E - 10 lks. | L-9 N¼ cor. Wood Post Spruce 4 S19°W - 07 lks. Spruce 4 N25°E - 06 lks. |
|--|---|--|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

| | | |
|---|---|--|
| K-9 Set by double the distance from the ¼ cor. west and a fence line north at the east 1/16 line and in centerline of E-W road. No evidence of original location. Fits original call on stream reasonably well. Prop. Dist. does not fit stream call. | K-10 Set from Tam. stub with very definite blaze for S.E. O.B.T. fits reasonable for prop. position | L-9 Set mid point and on line between the sec. corner west and the sec. corner east. |
|---|---|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|--|--|---|
| K-9 7" poplar S81°E - 163.4' Face of P.P. N 79° E - 154.8' East edge of Bridge Deck West - 466.2' | K-10 4" tam - N76°E 18.3' 4" tam - S87°E 12.5' 4" tam - S18°E 14.3' 1" pipe, 4" aluminum cap | L-9 5" poplar N41°E 89.3' Face of P.P. N70°E 98.8' South edge of blacktop - south - 3.1' South end of culvert S88°W 181.5' |
|--|--|---|

½" PIPE w/ PLASTIC R.L.S. CAP

½" PIPE w/ PLASTIC R.L.S. CAP

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE October 21, 1975
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)