

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 35 N. 8, R. 26 ^{NE} W.	J-7 K-7 K-8
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	T. 35 N. 8, R. 26 ^{NE} W.	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

MENOMINEE CO.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 12, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

J-7	K-7	K-8
Wood post	Wood Post	Wood Post
Beech 6 - S31W - 26	Lynn 12 - S66°E - 31	TAM 10 - S65E - 21
Do 4 - N34E - 12	Do 12 - N68°W - 13	Do 10 - N18W - 20

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-7	K-7	K-8	7
No mon. found set at intersection of roads E-W-S and in line with old fence north as being the best evidence for the proper location of this corner.	No mon. found set at intersection of roads E-W-N and in line with fence south as being the best evidence for the proper location of this corner.	Found 4"x4" cedar post stumps of both O.B.T.S MEA. exact but bearings do not check well.	Set mid point and on line between section cor. north and 1/4 cor. south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7	K-7	K-8	7
All 1" iron pipe with 4" aluminum cap - all bearings magnetic.	N.E. corner of conc. pad under mobile home - S45e -75.7'	4" cedar - N4E - 3.8'	9"h. maple
18" elm - S20°W - 73.4'	6" Elm S4E - 84.7'	4" cedar - N89W - 3.4'	S56E - 23.7'
Stop sign - S26°E - 49.2'			4" Tw. H. Maple
			S60W - 29.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE August 18, 1975

APPROVED AND SIGNED BY _____ DATE _____