

OCT 27 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/11 1999

Mr. David RLS
Chairman

For corners in

MENOMINEE
(County)

Located In:

Corner Cbde #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>35N</u> R <u>27W</u> | <u>M-7</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD
99 OCT 15 PM 1:42
PAGE # 27 BK 6
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49859

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNER A-7, T35N-R26W

I, William Lenca, in a field survey on Mar., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd - B.T.'s - Hemlock, 14" - S56°W - 38 lks; Hemlock, 16" - N72°W - 44 lks. All original evidence for this corner has been destroyed by farming activities.
- 1900: Section Subd. by Albert Hass shows this corner as it relates to other corners in Section 24, 35/27 and describes the monument as "Set 4 inch Cedar post from Gov't Bearing Tree" - Not evident.
- 1980: L.C.R.C. No. 262 by Gerald Carlson, RLS No. 24589 states set 5/8" x 24" iron w/RLS cap at c/l 4-way fence intersection - TIES: 3" Maple - N73°E - 27.63'; 14" Maple - S38°E - 5.38'; 3" Balsam - S86°W - 17.17'; 18" Maple - North - 9.76'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8" x 24" Iron Rod with RLS cap at the intersection of fences running North - South - East - West, and matching with the 4 B.T.'s as described in L.C.R.C. No. 262 (see part "A"). This corner position matches very closely with Albert Haas measurements to corners 1/2 mile West (2645.84 feet - Meas; Hass = 2645.28 feet) and 1 mile South (5306.98 feet - Meas; Hass = 5303.76'), and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" dia. x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner.

5" dia. Maple	N10°E	32.85 feet	Scr. NBT
7" dia. Maple	N76°E	40.49 feet	Scr. NBT
18" dia. Maple (Ex. B.T.)	S38°E	5.38 feet	Scr. NBT
5" dia. Cedar	S79°W	25.27 feet	Scr. NBT
Metal Survey Sign Post	N67°E	1.4 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Sep. 28, 1999