

SURVEY & REMONUMENTATION

APR 06 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. of 1990 On 5/19 1994
Mc Davis
Chairman

For corners in **SECTION**
MENOMINEE

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>26W</u>	<u>A-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
94 MAY 20 PM 3:3
PAGE # 62 BK. #
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49858
Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____
M-10 T35N-R27W

William Lenca, in a field survey on Apr. 5, 1994
to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL B.T.'s: Cedar, 22", S50°W, 13 lks
Hemlock, 19", N45°W, 33 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by County Road improvements.

PERPETUATION:

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Set corner in centerline of a North - South County Road and in line with an old fence line running East from the location. This position fits well with an old fence at the North 1/16 Line, and is accepted as the best available evidence for the position of the original corner.



3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set Berntsen A1NBF30 Monument stamped for corner:

8" dia. Cedar	Scr NBT	N53°E	37.45 feet
6" dia. Cedar	" "	S80°E	29.95 feet
8" dia. White Ash	" "	S48°W	41.76 feet
14" dia. Cedar	" "	N40°W	72.37 feet
Metal Survey Sign Post		West	31.9 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree. Witness Markers consist of 5/8" x 24" Iron Rods/2" Aluminum cap marked WITNESS MARKER.

Signed by William Lenca Date April 27, 1994
Surveyor's Michigan License No. 26461