

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/29 1998
Terence A. Wainio P.S.
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>27W</u>	<u>M-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD
98 DEC 14 PM 3:20
PAGE # 659 BKS
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

(SAME AS CORNER A-12, T35N-R26W.)

I, William Lenca, in a field survey on Oct., 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd - B.T.'s - Cedar, 6" - S80°W - 15 lks.; Spruce, 8" - N20°W - 08 lks. All original evidence for this corner has been destroyed by logging activities.
- 1994: Certified Survey Number 830 by William Lenca indicates he set a 2-1/2" x 30" Berntsen Monument / 3-1/4" cap at this corner. TIES: W. Ash, 5" - N38°E - 15.59'; W. Ash, 9" - S40°E - 27.13'; Maple, 9" - S48°W - 28.88'; W. Ash, 24" - N47°W - 28.89'; Carsonite Marker - S56°E - 2.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 2-1/2" diameter aluminum pipe with a 3-1/4 inch diameter aluminum cap and 4 B.T.'s as described in part A above. The corner falls at the intersection of ancient fences running East - West and North. This location fits well with measurements to corners 1/2 mile North and 1/2 mile South, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Existing 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

5" dia. White Ash	N38°W	15.59 feet	Scr. NBT
9" dia. White Ash	S40°E	27.13 feet	Scr. NBT
9" dia. Maple	S48°W	28.88 feet	Scr. NBT
24" dia. White Ash	N47°W	28.89 feet	Scr. NBT
Carsonite Marker	S56°E	2.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.



Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 29, 1998