

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

P.A. of 1990 On Dec 16, 1994

Mc Davis RLS
 ACTING Chairman

RECEIVED FOR RECORD
 4 DEC 27 AM 10:47
 REG # 177 BK 4
 SARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE COUNTY

Register of Deeds Stamp & File Number

For corners in
MENOMINEE
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey | T <u>35</u> N R <u>26</u> W | B-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	31	32	33	34	35	36							
12													
13													

I, William Lenca, in a field survey on Apr. 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL B.T.'s: Hemlock, 10", N41°E, 15 lks
- Hemlock, 5", N19°E, 06 lks

Original Survey by James H. Mullett in 1848. All original evidence for this corner has been destroyed by County Road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set corner on line with a fence line running North from this location and in line with the centerline of an East - West County Road. This position fits well with the record GLO distance west to the SW Corner of Section 30, and is accepted as the best available evidence for the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" diameter Aluminum cap - stamped for corner:

- | | | | |
|--|----------|-------|------------|
| 5" dia. Cedar | Scr NBT | N38°E | 45.33 feet |
| 5/8" x 24" Iron Rod/2" cap marked "Witness Marker" | | S50°E | 45.98 feet |
| 8" dia. Cedar | Scr. NBT | S41°W | 71.51 feet |
| 9" dia. Cedar | Scr. NBT | N51°W | 49.84 feet |
| Metal Survey Sign Post | | North | 30.5 feet |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date April 27, 1994
 Surveyor's Michigan License No. 26461