

# SURVEY & REMONUMENTATION

JAN 09 2001

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. of 1990 On 7/13, 2000  
Me. Davis RLS  
Chairman

Book 6 Page 143

For corners in <u>MENOMINEE</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>35N</u> R <u>26W</u>	D-01	
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
	T ___ R ___	_____	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	_____
	S ___ T ___ R ___	_____	_____

RECEIVED FOR RECORD  
13 DEC 2000 10:16:09 A  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
SAME AS CORNER D-13 T36N-R26W

I, William Lenca, in a field survey on May 25, 1900 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1				●									
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 12" - N65°E - 19 lks.; Cedar, 12" - N79°W - 20 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1987: L.C.R.C. No. 769 by William Lenca, RLS No. 26461 - Set Railroad Spike in centerline of Co. Rds E-W-N and in line with old fence South. B.T.'s: Power Pole - N40°W - 48.14'; W. Birch, 5" - South - 38.73'; W. Birch, 6" - S54°W - 63.25'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

We found a Railroad Spike and 3 Witnesses as described in L.C.R.C. No. 769 (see part A). This position fits well with existing lines of occupation, has been accepted and used as control for surveys in the area, and is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

8" dia. Elm	N34°E	75.06 feet	Scr. NBT	
8" dia. Cedar	S27°E	37.85 feet	Scr. NBT	
9" dia. Cedar	S52°W	62.85 feet	Scr. NBT	
5/8" x 24" Iron Rod/plastic Ident. cap	N41°W	47.38 feet	1.0' E. of Power Pole	
Metal Survey Sign Post	South	31.65 feet		



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Aug. 8, 2000