

# SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1990 On 12/30 1997  
McL Davis RLS  
Chairman

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in  
MENOMINEE  
(County)

Located In:	Corner Code #
1. Public Land Survey	T <u>35</u> N R <u>26</u> W I-03
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S ___ T ___ R ___
	S ___ T ___ R ___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

REGISTERED FOR RECORD  
97 DEC 30 PM 4:06  
PAGE # 6-22, BK 5  
BARBARA JOHNSON  
REGISTERED PROFESSIONAL  
SURVEYOR  
LICENSE NO. 36461

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Oct. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3									●				
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Beech, 14" - N46°W - 17 lks.; Hemlock, 10" - S60°W - 20 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a railroad spike in the centerline of an East - West county road and in line with an old fence to the South. The distance to the 1/4 corner to the East is 2826.66 feet, however, measurements to the 1/16 corner and 1/4 corner to the West are normal and fit this occupation well. Also, the occupation at the West 1/4 Corner and Southeast Corner corroborate this position, and it is therefore accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

6" dia. Cedar	N54°E	76.13 feet	Scr. NBT
4" dia. Hemlock	S43°E	75.08 feet	Scr. NBT
14" dia. Maple	S36°W	79.96 feet	Scr. NBT
8" dia. Cedar	N25°W	52.97 feet	Scr. NBT
Metal Survey Sign Post	North	28.9 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 18, 1997

