

**SURVEY &  
REMONUMENTATION**

**JAN 09 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. Of 1990 On 7/13, 2000  
William Lenca  
Chairman

*Book 6 Page 173*

For corners in  
MENOMINEE  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>35</u> N R <u>26</u> W	I-6
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECEIVED FOR RECORD  
13 DEC 2000 10:16:09 A  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Oct., 19 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15	●	14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Beech, 4" - N43°W - 8 lks.; Beech, 8" - N37°E - 29 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1991: L.C.R.C. No. 910, Book 3, by William Lenca, RLS No. 26461 states "Set 5/8" x 24" Iron Rod/Ident. cap on line between Section corners and midway between fences running on North and South sides of an East-West County Road. TIES: Nail in 12" W. Ash, S62°E, 16.91'; Nail in 5" Maple, S14°E, 25.94'; Nail in 9" W. Ash, S62°W, 28.46'; Nail in 20" W. Ash, N40°W, 45.00'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 5/8 inch x 24 inch iron rod/Identification cap and 4 B.T.'s in place as described in L.C.R.C. No. 910 (see part A). The corner falls on line between Section Corners 1/2 mile North and 1/2 mile South and midway between old fences on the North and South sides of and East - West County Road. This position has been used as control for surveys in the area, fits existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" dia. x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner.

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N60°E	47.54 feet	2.1' NW of 9" Apple
12" dia. White Ash (Existing B.T.)	S62°E	16.91 feet	Scr. NBT
9" dia. White Ash (Existing B.T.)	S62°W	28.46 feet	Scr. NBT
20" dia. Black Ash (Existing B.T.)	N40°W	45.00 feet	Scr. NBT
Metal Survey Sign Post	South	2.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Nov. 16, 2000