

MAR 29 2000

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1999 On 10/23 1999
McL Davis DLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MENOMINEE
(County)

Located In: Corner Code #

- | | | |
|---------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>35</u> NR <u>26</u> W | <u>I-10</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

BK. 6 Pg. 82

RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 10" - S43°E - 11 lks.; Cedar, 10" - N55°W - 11 lks. All original evidence for this corner has been destroyed by logging activities.
1975: L.C.R.C. No. 116 by David Babbitt, RLS No. 21558, states "Fd. 4" x 4" Sq. Ced. Post & point of another post, old signature tree nearby dated 1936, and other dates - signed Slater." Set 1" pipe, 4" aluminum cap. B.T.'s: Cedar, 7" - S55°W - 4.1'; Cedar, 5" - N30°E - 6.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1 inch diameter iron pipe with 4 inch dia. aluminum cap and 2 B.T.'s as described in L.C.R.C. No. 116 (see part "A") by retracement of a 1975 DNR Survey. This corner has been used by local surveyors for more than 60 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Existing 1-1/2" dia. Iron Pipe/4" Alum. Cap stamped for corner location.

7" dia. Cedar (Ex. B.T.)	N30°E	6.54 feet	Scr. NBT
10" dia. Cedar	S25°E	11.46 feet	Scr. NBT
7" dia. Cedar (Ex. B.T.)	S55°W	4.55 feet	Scr. NBT
6" dia. Cedar	N65°W	18.00 feet	Scr. NBT
Metal Survey Sign Post	South	1.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Aug. 30, 1999