

**SURVEY &
REMONUMENTATION**

JAN 09 2001

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. Of 1990 On 12/22 2000
Mel Anni RLS
Chairman

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>35</u> N R <u>26</u> W	I-12
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Bk. 6 Pg. 239

RECEIVED FOR RECORD
28 DEC 2000 2:31:31 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Dec., 19 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Tamarack, 4" - S60°W - 53 lks.; Tamarack, 8" - N57°W - 55 lks. Remains of both B.T.'s were found as described in L.C.R.C. No. 106, Book 1.
- 1975: L.C.R.C. No. 106, Book 1, by David B. Babbitt, RLS No, 21558 states "Found 4" x 4" Tam. post lying down in swamp muck stumps for both original bearing trees but S.W. one is S60°W not S6°W as recorded. S.W. stump shows plain lower face but no scribe marks. N.W. stump mostly rotted away. Set standard D.N.R. mon. & 5" x 5" square cedar post." TIES: (N.B.T.) Cedar 2", N68°W, 37.8'. No other near.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1inch diameter iron pipe with a 4 inch diameter aluminum and 1 B.T. in place as described in L.C.R.C. No. 106, Book 1 (see part A). As stated in the above corner record, this corner was re-set from original B.T.'s and is therefore accepted as a careful and faithful perpetuation of the position of the original corner. The corner falls in a large blueberry marsh area with no natural witnesses nearby.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted Existing 1" dia. Iron Pipe/4" Alum. Cap stamped for corner location.

2" dia. Cedar (Ex. B.T. - rec. as 37.8 feet) N68°W 38.2 feet to nail Not Scribed
Nothing else nearby
Metal Survey Sign Post North 1.5 feet



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 13, 2000