

SURVEY & REMONUMENTATION

FEB 11 1998

P.A. of 1850 Ga

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 35N R 26W

J-03

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTERED FROM RECORDS

97 DEC 30 PM 4:05

PAGE # 633, BK 5

REGISTERED FROM RECORDS

REGISTERED FROM RECORDS

REGISTERED FROM RECORDS

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on Oct. 30, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|---|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Fir, 4" - S02°E - 18 lks.; Cedar, 4" - N54°E - 13 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a Bernsten W-1-B Road Monument with the cap broken off. The monument falls in the centerline of an East - West county road and in line with an old fence to the North. My private records indicate that in a 1986 survey we established this corner in accordance with existing lines of occupation. We removed the broken Bernsten Monument and replaced it as described in part "C" below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

| | | | |
|------------------------|-------|------------|----------|
| 5" dia. White Ash | N34°E | 38.51 feet | Scr. NBT |
| 6" dia. Double Maple | S37°E | 87.03 feet | Scr. NBT |
| 9" dia. Hemlock (Ex.) | S07°W | 60.60 feet | Scr. NBT |
| 7" dia. Cedar (Ex.) | N37°W | 72.38 feet | Scr. NBT |
| Metal Survey Sign Post | South | 48.70 feet | |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 18, 1997

