

SURVEY & REMONUMENTATION

JAN 09 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. Of 1990 On 7/13, 2000
M. N. RLS
Chairman

Book 6 Page 180

For corners in
MENOMINEE
(County)

Located In:	Corner Code #	
1. Public Land Survey	T <u>35N</u> R <u>26W</u>	<u>K-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD
13 DEC 2000 10:16:09 A
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Sep., 19 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2	●	1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Beech, 12" - S50°E - 8 lks.; Beech, 4" - N82°W - 18 lks.; All original evidence for this corner has been destroyed by County Road improvements.

1986: L.C.R.C. No. 740, Book 3, by William Lenca, RLS No, 26461 states "Set 30" long aluminum monument with 4" cap marked MENOMINEE COUNTY SURVEY MARKER in line with centerline of county road North-South in location indicated by existing lines of occupation. Existing lines of occupation fit closely with GLO measurements of this line."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a W-1-B Berntsen Monument in place in the centerline of a North - South County Road and in line with and old fence line running East as described in L.C.R.C. NO. 740 (see part A). The measurement from this corner North to the Section corner is 2969.79 feet compared to the GLO record distance of 2976.6 feet. This corner has been used as control for surveys in the area for at least 14 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing W-1-B Berntsen Monument/4" dia. Alum. cap stamped for corner location:

6" dia. Norway Pine	N38°E	72.86 feet	Scr. NBT
8" dia. Norway Pine	S70°E	47.95 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	West	27.19 feet	@ Survey Sign Post
Metal Survey Sign Post	West	27.9 feet	
Nothing Else Nearby			

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 16, 2000