

SURVEY & REMONUMENTATION

JAN 09 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. Of 1990 On 7/13, 2000
Mike Davis RLS
Chairman

Book 6 Page 183

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>35N</u> R <u>26W</u>	K-9
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECEIVED FOR RECORD
13 DEC 2000 10:16:09 A
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Sep., 19 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 10" - N58°W - 12 lks.; Cedar, 8" - S32°E - 44 lks.; All original evidence for this corner has been destroyed by County Road improvements.
- 1975: L.C.R.C. No. 115, Book 1, by David B. Babbitt, RLS No. 21558 states "Found no evidence of original location. Set 1/2" pipe with plastic R.L.S. cap by double the distance from the 1/4 corner west and a fence line north at the east 1/16 line and in centerline of E-W road. Fits original call on stream reasonably well. Prop Dist. does not fit stream call. TIES: Poplar 7", S81°E, 163.4'; Face of Power Pole, N79°E, 154.8'; Bridge Deck West, 466.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The corner described in L.C.R.C. No. 115, Book 1 (see part A) has been destroyed by county road improvements. The bridge referred to in the above corner record has been reconstructed, and only the stump of the Power Pole tie remains. We had previously recovered the Quarter Corner 1/2 mile West. We also found a 1/2 inch diameter iron pipe set for the West 1/16 Corner on the South Line of said Section by David Babbitt. We projected this line East and doubled the distance between these 2 corners to re-establish the destroyed corner. This position fits well with the stump of the power pole used as a tie in L.C.R.C. No. 115. We accepted this corner location as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N76°E	154.86 feet	1' S. of Power Pole
8" dia. Willow	S70°W	94.80 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	North	25.61 feet	@ Survey Sign Post
Mctal Survey Sign Post	North	26.3 feet	
Nothing Else Nearby			



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 17, 2000