

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> (County)	Located In:	Corner Code <i>≠</i>
1. Public Land Survey	T <u>35N</u> R <u>27W</u>	<u>K-6.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David B. Babbitt, in a field survey on 10/18, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-6. East one quarter corner of Section 14. Wood post. 1848, Sugar 16, S43W, 11 Lks.
 Birch 4, S55E, 15 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6. Set DNR monument at very old fence corner with fences N-S-E & W. This monument is nearly MPOL between section corners based on $\frac{1}{2}$ of road and record mea. north of a small stream for the NE section corner of Section 14. (No monument found or set for said NE section corner).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6. DNR Monument.
 21" sugar maple, N43E, 67.85'
 17" twin sugar maple, N86E, 88.7'
 10" cherry, S07W, 33.5'
 Fence Post, N77W, 3.6'

PK w/reference tag in fence post.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by David B. Babbitt

Date 11-29-89

Surveyor's Michigan License No. 21558