

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. of 1990 On 10/31 1997
Mc Davis DLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T36N R. 27W T35 R 28 T 35 R 27 T R S T R	A-13 M-1 A-D M-13
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

57 NOV 21 PM 3:17
REGISTER OF DEEDS
MENOMINEE COUNTY
MICHIGAN
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNERS M-13, T36N-R28W; A-1, T35N-R27W; M-1, T35N-R28W

I, William Lenca, in a field survey on Sept 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	20		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1847: Original Survey by H. Floyd - B.T.'s - Cedar, 11" - N33°E - 42 lks.; Tamarack, 8" - N10°W - 20 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

My private records indicate that in a 1993 survey we established this corner in the centerline of an East - West County Road and at a single proportionate distance between the S1/4 of Section 36, T36N - R28 and the S1/4 of Section 31, T36N - R27W and monumented this position with a railroad spike. We recovered this railroad spike and accepted it as a careful and faithful reestablishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Sct 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

10" dia. Cedar	N43°E	62.90 feet	Scr. NBT
6" dia. Elm	S49°W	59.84 feet	Scr. NBT
12" dia. White Pine	N18°W	60.97 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	South	25.53 feet	
Metal Survey Sign Post	South	26.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 13, 1997

519