

APR 06 1999

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/30, 1998

Mc Davis RLS  
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>27W</u>	<u>B-11</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling In Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECEIVED FOR RECORD  
99 JAN - 6 AM 8:54  
PAGE # 711 DRK-  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on May 21, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11	31		32		33		34		35		36	
12												
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Birch, 4" - S08°E - 05 lks.; Cedar, 6" - N50°W - 22 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1958: Survey by Irvin Grassl shows this corner as it relates to other corners in Gov. Lot 1, Sec. 31. The corner is described as a "Gov't Monument".
- 1964: Plat of Survey by Robert Olsen, RLS 10700, shows a steel pin for this corner.
- 1990: L.C.R.C. Number 884 by William Lenca states, "Found 1" diameter Iron Rod on South edge of county road from information contained in a 1958 survey by Irvin Grassl and in a 1964 survey by Robert Olsen." TIES: Maple, 24" - N89°E - 65.83'; W. Ash, 5" - S51°E - 76.78'; W. Ash, 5" - S03°E - 49.60'; Power Pole - N78°W - 106.93'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1 inch diameter x 18 inch iron over a 1/2" diameter Iron 2-1/2' below a county road surface. This location falls in line with the centerline of a county road to the West and fits well with existing monuments along the North Line of Section 31 as shown in the 1958 survey by Irvin Grassl and the 1964 survey by Robert Olsen. The location of the existing monument was accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location:

24" dia. Maple	N87°E	65.78 feet	Scr. NBT
10" dia. White Ash	S10°E	58.10 feet	Scr. NBT
7" dia. White Ash	S51°E	76.78 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S52°W	38.68 feet	1' N. of Twin 8" W. Ash
Metal Survey Sign Post	S14°E	29.7 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.



Signed by William Lenca

Date Dec. 22, 1998

Surveyor's Michigan License No. 26461