

APR 0 6 1998

SECTION

Approved by Menominee County
Land Survey Rememoration
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/30 1998
Mel Davis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35</u> N R <u>27</u> W	<u>C-10</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD
99 JAN - 6 AM 8:55
PAGE # 715 BK 5
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE MI 49833

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Mar. 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Tamarack, 14" - S40°W - 05 lks.; Tamarack, 10" - N40°E - 06 lks. Rotted remains of stumps still evident.
- 1984: L.C.R.C. Number 603 by George B. Wilson states, "FOUND 2 ORIG. B.T.'S AND OLD STAKE 12" UNDER GROUND." Set 4" dia. Berntsen HDR Monument. TIES: Deep 1 set 2' North and 2' East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4 inch diameter aluminum rod with 3-1/4 inch diameter aluminum cap (Berntsen HDR Monument) and rotted remains of 2 tamarack stumps fitting the position of the original bearing trees. We accepted the position of the HDR Monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" dia. x 5' long Aluminum Rod/3-1/4" dia. Alum. cap stamped for corner location:

8" dia. Cedar	N37°E	25.53 feet	Scr. NBT
10" dia. Cedar	S67°E	32.66 feet	Scr. NBT
10" dia. Cedar	S36°W	9.95 feet	Scr. NBT
10" dia. Cedar	N64°W	13.19 feet	Scr. NBT
Metal Survey Sign Post	West	0.9 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 22, 1998

