

MAR 29 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/11 1999
Mac Davis RLS
Chairman

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35</u> NR <u>27</u> W	<u>E-02</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Bk. 6 Pg. 98

RECEIVED FOR RECORD
28 DEC 1999 3:56:09 PM
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Oct., 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5	●	4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	10			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Sectional Subdivision by James H. Mullett - B.T.'s - Hemlock, 10" - S37°E - 13 lks.; Hemlock, 5" - S44°W - 26 lks. All original evidence for this corner has been destroyed farming activities.
- 1895: Plat of Survey by Justus Little recorded in Record of Survveys book in Register of Deeds Office shows this corner as it relates to other corners in Section 4, T35N-R27W. No monument is described and no ties are given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Due to clearing and farming activities and county road improvements in the area, we were unable to recover any evidence of the corner placed by Justus Little in 1895. We accepted a position in line with the centerline of county roads running East and South and in line with an ancient fence line running West. The measurement from this location to the corner 1/2 mile North is 2543.12 feet compared to the GLO record of 2544.3 feet. The measurement to the corner 1/2 mile South is 2633.98 feet. Since the existing occupations and measurements agree well with this location, we accepted it as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2"dia. Aluminum Pipe 30" long 3/4" dia. Alum cap stamped for corner location:

11" dia. Apple	N58°E	47.10 feet	(Not Blazed)
10 dia. Elm	S45°E	50.42 feet	Scr. NBT
Nothing Else Nearby			
Metal Survey Sign Post	West	3.60 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Nov. 2, 1999