

SURVEY & REMONUMENTATION

APR 06 1999

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 945 Of

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

P.A. Of 1990 On 10/29, 1998
Terrence J. Wanie PS.

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35</u> N R <u>27</u> W	<u>E-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD
 98 NOV 16 AM 9:59
 CLERK
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on June 09, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 6" - S86°E - 09 lks.; Cedar, 7" - S38°W - 12 lks. All original evidence for this corner has been destroyed by logging activities.
- 1984: L.C.R.C. Number 603 by George B. Wilson states, "FOUND 2 ORIG. B.T.'S" - Set 4" dia. Berntsen HDR Monument. TIES: Deep 1 set 2' North and 2' East.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Berntsen HDR monument which was set from 2 original bearing trees as indicated in Land Corner Recordation Certificate Number 603 by George B. Wilson, RLS No. 17607. Also found were 4 new bearing trees with an "x" cut in the upper and lower blazes. This position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing HDR monument:

9" dia. Black Spruce	N38°E	11.55 feet	Ex. BT - Cross cut upper & lower Blaze
12" dia. Cedar	S61°E	9.66 feet	Ex. BT - Cross cut upper & lower Blaze
8" dia. Cedar	S56°W	7.15 feet	Ex. BT - Cross cut upper & lower Blaze
9" dia. Cedar	N54°W	16.59 feet	Ex. BT - Cross cut upper & lower Blaze
Metal Survey Sign Post	North	1.15 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 21, 1998

